



---

EP18/19 – 23

Request for Proposal Specifications

Multiplex Addressable Fire Alarm System Installation

---

**RFP Coordinator:**

Erin DelleFemine

Controller/Purchasing Agent

City of East Providence

[edellefemine@cityofeastprov.com](mailto:edellefemine@cityofeastprov.com)

**Technical Contact**

Ed Catelli

Superintendent of Public Buildings

City of East Providence

[ecatelli@cityofeastprov.com](mailto:ecatelli@cityofeastprov.com)

## **Project Scope:**

The City's Public Works building located at 60 Commercial Way seeks the installation of a new Multiplex Addressable Fire Alarm System, preferred manufacturer shall be Notifier.

## **Specifications:**

The Contractor shall furnish and install a new Mutliplex Addressable Fire Alarm System throughout the facility as required by NFPA, the RI Uniform Fire Alarm Code, the National Electrical Code and the local A1-1.1. (East Providence Fire Department).

Vendor shall be able to demonstrate extensive experience with the design and installation of complete fire alarm systems in similar facilities if required. Also, vendor shall be fully licensed in the state of RI to perform this work.

Vendor shall provide complete drawings including a stamp from a Registered RI Professional Engineer.

Vendor shall obtain approvals on design from the EPFD prior to start of any work.

Wiring method shall be Fire Alarm MC cable concealed and EMT for surface/exposed applications.

Include all lifts, scaffolding, ladders and equipment to completely perform the work,

Include fees for required permits and fire department plan review and inspections.

Confirm with Fire Department if existing radio master box can be re-used. If not, furnish and install new radio master box. Confirm Radio master box zoning with the EPFD.

Include quarterly testing contract for the first year.

Furnish and install a new key lock box as required.

Include complete demolition of the existing system, once new system is accepted by the fire department and placed on line and is fully operational.

Furnish and install new ceiling tile damaged by construction and where existing devices are being removed.

Include any patching and painting of disturbed surfaces.

Blank off any existing boxes that are flush or cannot be removed.

All waste shall be removed from the site by the vendor on a daily basis and be legally disposed of.

Provide complete As-Built drawings and O&M Manuals at the completion of the project.

**A walk through will be held at 60 Commercial Way, East Providence RI 02914 on Wednesday, October 2, 2019 at 10:00 AM. Those who wish to submit a bid are strongly advised to attend.**

**Bid opening Tuesday, October 15, 2019 at 11:00 AM.**