

**CITY OF EAST PROVIDENCE
PUBLIC BUILDINGS DIVISION**

**RFP: TWO FIVE TON NATURAL GAS HVAC SYSTEMS
BID EP15/16 – 23**

SPECIFICATIONS

Scope of work for replacement of **Two Five Ton HVAC Units and Ducting Systems** at Breed Hall

- Disconnect and remove the old units and exterior ductwork.
- Install curbs, or welded stands on the pads to raise the units and lift the new units into place.
- Connect gas pipe, and paint pipe safety yellow
- Wire high voltage with new disconnect and fire alarm shut down
- Re-connect low voltage
- Setup economizers and drains
- Install new ductwork from the units to the supply and return at the building wall
- Exterior insulation and jacket the new ductwork
- Startup and test units for proper operation
- The current electrical requirements are 208/230 Volt single phase